

## NuMI Target Hall Performance/Plans

Jim Hylen
DOE Tevatron Operations Review
March 27, 2007

#### Outline




- Overview of target hall
   and target/horn experience
- Summary of problems causing 1 day or more downtime, and corrective actions underway
- (back-up slides describing individual problems)
- Spares status
- Plans for target with evolving beam conditions

2




## How NuMI v beam is produced


120 GeV/c protons strike graphite target
Magnetic horns focus charged mesons (pions and kaons)
Pions and kaons decay giving neutrinos



Design for 0.4 MW proton beam



## Target for Low Energy Neutrino Spectrum





#### Experience with the NuMI Target


 $\overline{1}^{\text{st}}$  Target took beam for over a year, 820 MWhr integrated beam power. Two problems:

- water leak soon after turn-on; back-pressure with Helium to keep water out
- target motion drive shaft froze up after year of operation stuck in H.E. focus  $2^{nd}$  Target is running (no leak)

	Max. Proton/spill	Max. Beam Power	Integrated Protons on Target			
Target Design specification	40e12 p.p.p.	400 kW	370 e18 p.o.t. lifetime			
1 <sup>st</sup> target Before leak	25e12 p.p.p. 11e12 day before leak	69 kW	0.7 e18 p.o.t.			
1 <sup>st</sup> target After leak	30e12 p.p.p.	270 kW	158 e18 p.o.t.			
2nd target	40e12 p.p.p.	320 kW	105 e18 p.o.t.			



## $\frac{\text{Magnetic Horns}}{\pi \text{ focused by toroidal field between conductors}}$



- 3 m long focusing region
  - > Achieved ~ 0.1 mm radial tolerance after weld

Inner conductor dominated by joule heating
 Outer conductor dominated by beam heating

Drain






Parabolic inner conductors:

- 3 Tesla max. magnetic field
- 3 m active length each horn

Inner conductors welded together at FNAL by lead engineer Kris Anderson








Horns in target hall June 2004

1st run with beam Jan. 2005

Accumulated:

15 Million pulses

1,350 MWhr integrated beam power



Still running with first set of horns



### Target Hall during construction














#### Work cell

Target module in beam-line

1st target being removed





#### NuMI work cell for radio-activated components



Shown during test-assembly above ground

Lead-glass windows (not shown)

Remote controlled door

Remotely installable top shielding



# All NuMI target hall beam components and innermost shield layers are installed /removed remotely with crane and cameras





Crane includes remote hook rotation.

Steel shielding block being moved.

# 华

## Big Picture of Maintenance

- NuMI target hall is a difficult system
  - > High radiation forces remote handling
    - repairs take a long time
  - > Target hall is nasty environment
    - E.g. humidity has PH of 2.6, very corrosive
    - · Limited list of materials are rad-hard enough
  - > Interventions are time-consuming
    - Access to components requires 1 shift just to put electronics back on target hall crane
    - Must un-stack, then re-seal shielding each access
    - · Components are an order of magnitude larger than Pbar's


Achieving high up-time requires design of robust components


Biggest current concern:

- If you have no spare - you must repair!
- > Producing an adequate supply of spare horns
  - · Usually replacement takes less time than repair



### NuMI Performance - POT/week







# Up (513) and down (83) days 5/1/05 - 3/22/07 86% / 74% efficiency excluding / including sched. shutdown

Days	Description (**non-recurring)	Long term corrective action			
513	Up for beam				
95	Accelerator scheduled down				
25	Horn cooling spray clog **	Check valves, filters on skids			
14	Horn water line repair	Eliminate braze on spares			
14	Target motion frozen	Graphalloy bushing on spare			
10	Horn ground fault	Pin feet, float modules			
8	Tritium mitigation **	Condensate sys./dehumidifiers			
6	Replace NuMI beam-line magnet				
4	Replace accelerator magnet				
2	Replace pile chiller compressor	New hot spare chiller unit			



## Other long term actions

## Corrosion protection


- > Improve dehumidification of target pile
  - Planned installation summer 2007
- > Selection of materials
  - E.g. stainless sheathing instead of nickel coating of shielding on remote electrical clamp for spares

## Accelerate production of spares


- > Batch process horns
  - · Doing several at once is much more efficient
- > Engineer hired specifically for spare horn welding
- > Tech. assigned specifically to track parts



June 30, 2006, resin beads from deionization bottle clogged the water spray lines on Horn 1



New, uncontaminated beads Beads are ~ 20 mils diameter






Horn nozzle for inner conductor is eliptical ~40 mils short direction (48 total)

outer conductor nozzles round, 25 mils diameter (19 total)

plus two side-spray nozzles





When water skid was turned off for maintenance, beads floated backwards through improperly mounted check valve




The gravity un-assisted check valve



### Fan push, water-in-barrel filter, vacuum şuck

Cleaning Out Resin Beads





#### Two horn water system leaks: Horn 2 in February 2006, Horn 1 in August 2006


Have brazed ceramic electrical insulators on horn water lines They are strain-relieved with invar+ceramic clam-shells

On horn 1, developed a 7gal/day water leak on line to spray header

On horn 2, leak on suction line drew air in, reducing amount of water ejector pump could remove from horn collection tank

Both ceramic sections were successfully replaced


Speculate braze corrodes...
planning to switch from brazed
to a shrink-fit ceramic/steel
connection for spare horns





#### High dose rates made Horn 1 ceramic replacement challenging

75 r/hr (0.75 Sv/hr) on contact 35 r/hr (0.35 Sv/hr) at 1 foot



	@ 1 foot On Contact				
Point	(mr/hour)	(mr/hour)			
1	35000	75000			
2	40000	75000			
3	35000	80000			

Doserate Doserate

Repair people got weekly dose limit in a few seconds



#### Shielding for Horn 1 ceramic repair job




Built an extension of the work-cell with window for work

( Horn is in work-cell, behind the door )



#### Mock-up and practice for repair



Plan, time, and practice, practice, practice repair

Needed to undo two
Swagelok fittings,
remove old section,
insert new section,
and tighten two fittings.

Time est: 2 min. of actual work in slot

Dose for this "2 min." job was 371 mr, (3.7 mSv) divided over ~10 people.

The rest of job is in much lower radiation field, but dose can be non-negligible due to time involved.




#### Frozen drive shaft on target motion system


After month-long test in High Energy position drive shaft will not rotate to move target into Low Energy position


On target carrier #3, change to Graphalloy bushing

Old jammed pillow-block












Horn 2 before beam

1.5 inch clearance foot to floor


Owl shift Thurs. Sept. 29, 2005 intermittent horn trips.
Owl shift Sat. Oct. 1, hard ground fault of 1 ohm.
-removing stripline fingers Horn 2 + stripline block
-when Horn 2 moved to work cell ground fault cleared
-foot left behind in chase, nut had vibrated off


Moved old foot, installed new foot


-scorch marks seen under foot











Horn is corroding – eventually will have to replace it



## Spares Status - Horns and target

HORNS	PH1-00	PH1-01	PH1-02	PH1-03	PH1-04	PH1-05	PH2-01	PH2-02	PH2-03	PH2-04
in use	proto	in use					in use			
fiducialize (survey)										
instrumentation										
water tank, hangers										
test pulse			2/3							
stripline								silvered		
water lines etc										
I.C.+O.C assem										
O.C. silvered										
O.C. coated										
O.C. welds										
O.C. machined										
O.C. blanks										
I.C. silvered										
I.C. coated										
I.C. welds			7/7	3/7	3/7	3/7		6/6	5/6	
I.C. machined										5/7
I.C. blanks										
					700kW	700kW				700kW
TARGETS	NT-01	NT-02	NT-03	NT-04						
in use	stuck	in use	141 00	141 04						
fiducialize (survey)	in	III use								
instrumentation	H.E.									
hangers	posn.						Color co	nde		
mount target + baffle	Poor						23101 00	Used		
fab carrier								Done		
fiducialize target								In progress		
fab target + baffle				ordered				to do		




## Plan for target for evolving beam condition

#### Existing target was designed for 4.0e13 p/pulse, 400kW

- After summer shutdown, slip-stacking may provide up to
   4.5e13- 4.8e13 p/pulse, 400 kW (when pbar source not running)
  - ▶ By increasing beam spot size to 1.2 mm RMS for 4.5e13, will have same stress as current 1.0 mm RMS for 4.0e13 on target
  - > Have tested larger spot size, baffle scraping by beam still fine
  - Preliminary Monte Carlo indicates negligible impact on neutrino spectrum

28




## Plan for target for evolving beam condition


For NOVA experiment (2011), target no longer needs to fit in horn → M.E. target design

- With ANU sub-project, beam specification is
   4.9e13 p/pulse, 700 kW
  - ▶ By increasing beam spot size to 1.3 mm RMS, will have same stress as current 1.0 mm RMS for 4.0e13 on target
  - > Moving water cooling further from beam-spot reduces water-hammer
  - > Still work to do on window and outer casing cooling, but does not appear to be any show-stoppers



## Medium Energy Target for NOVA running





## Plan for target for evolving beam condition

A possible next stage for beam after ANU is to re-use Accumulator Ring

Plan to use essentially same NOVA M.E. target design

- With Accumulator, beam specification could be 8.3e13 p/pulse, 1200 kW
  - $\triangleright$  By increasing beam spot size to 1.5 mm RMS, would have calculated stress safety factor of  $\times 1.4$  on graphite
  - Still work to do on window and outer casing cooling, but appears doable